

Subdivisions, T. 3, N. R. 29 E.

Chains	
	North between Sections 15 & 16. Variation 20° 05' East.
27.00	Leave Bottom, course bears N.W. & S.E.
36.25	Road bears N.W. & S.E.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
46.00	In dry ravine, bears East and West.
80.00	Set post for corner to Secs. 9, 10, 15 and 16, in mound of earth &c., as per instructions.
	Land, gently rolling.
	Soil, 2nd rate.
	September 19th, 1859.
	East on random line between Secs. 10 & 15.
40.00	Set post for temporary 1/4 Sec. corner.
79.56	Intersect N. & S. Line 34 links South of Sec. corner. S. 89° 45' W. on true line between Secs. 10 & 15.
39.78	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
79.56	The corner to Sections 9, 10, 15 and 16.
	Land, level.
	Soil, good 2nd rate.
	North between Sections 9 and 10. Variation 20° East.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
68.20	Indian trail, bears E & W.
80.00	Set post for corner to Secs. 3, 4, 9 & 10 in mound of earth &c., as per instructions.
	Land, gently rolling.
	Soil, good 2nd rate.
	East on random line between Secs. 3 & 10.
40.00	Set post for temporary 1/4 Sec. corner.