

## Subdivisions ,T. 3, N. R. 29 E.

Chains	
42.50	Enter Bottom; course bears East & West.
80.00	Set post for corner to Secs. 7, 8, 17 & 18, in mound of earth &c., as per instructions.
	Land, level.
	Soil, 1st rate.
<hr/> East on a random line between Sections 8 & 17.	
40.00	Set post for temporary 1/4 Sec. corner.
52.50	Umatilla River, runs West; offset 500 links North; thence East intersect N. & S. Line at 80.40 chs., 300 links North of Witness corner, making the bearing of the true line S. 89° 39' W.
	S. 89° 39' W. on true line between Secs. 17 & 8.
27.90	Leave River, course bears N. 85° W.
40.20	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.40	The corner to Secs. 7, 8, 17 & 18.
	Land, level.
	Soil, 1st rate.
<hr/> West on a random line between Secs. 7 & 18.	
40.00	Set post for temporary 1/4 Sec. corner.
87.70	Intersect West boundary 73 links North of Section corner. N. 89° 29' E. on true line between Secs. 7 & 18.
47.70	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
87.70	The corner to Secs. 7, 8, 17 & 18.
	Land, level.
	Rich Bottom.
<hr/> North between Sections 7 & 8.	
	Variation 19° 50' East.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 5, 6, 7 & 8 in mound of earth &c., as per instructions.