

W. Bdry., T. 3 N. R. 30 E.

Chains

From the established corner to Townships 3 and 4 North of Ranges 29 and 30 East, run East on a random line on North boundaries of Secs. 6, 5, 4, 3, 2 and 1.

Variation 20°15' East

Set temporary half mile and mile posts at every 40 and 80 chains, and at 6 miles, 6 chains, and 17 links intersected the guide meridian at the corner of Townships 3 North of Ranges 30 and 31 East. The correction will, therefore, be 6.17 chains West per mile, and the true course of line West.

North boundary T.3 N. R. 30 E.

West on true line between Sections 1 and 36.

40.00 Set post for $\frac{1}{4}$ Sec. corner, and established the same in earth mound as per instructions.

80.00 Set post for corner to Sections 1 and 2, 35 and 36 in earth mound established as per instructions.

Land, gently rolling.

Soil, 2nd rate.

West on true line between Sections 2 and 35.

Variation 20°30' East

40.00 Set post for $\frac{1}{4}$ Section corner in earth mound established as per instructions.

80.00 Set post for corner to Sections 2 and 3, 34 & 35 in mound of earth established as per instructions.

Land, gently rolling.

Soil, 2nd rate.

West on true line between Sections 3 and 34.

Variation 22° East.

22.00 Trail, course North and South.

40.00 Set post for $\frac{1}{4}$ Section corner in mound of earth, established as per instructions.