

Subdivisions, T. 3 N., R. 3 E.

Chains 79.74	The corner to Secs. 15, 16, 21 & 22. Land and soil same as last mile.
40.00	North between Secs. 15 & 16. Set a post for quarter sec. corner and drove a charred stake and raised mound of earth, with trench and pits, as per instructions.
80.00	Set a post for corner to Secs. 9, 10, 15 & 16. Drove a charred stake and raised mound of earth with trench and pits, as per instructions. Land, gently rolling prairie. Soil, good 2nd rate.
40.00	East on a random line between Secs. 10 & 15. Variation 21° 00' E. Set a temporary quarter sec. post.
80.38	Intersect corner to Secs. 10, 11, 14 & 15 at post. West on a true line between Secs. 10 & 15.
25.38	To Indian Trail, course N & S.
40.19	Set a post for quarter section corner. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.
80.38	The post corner to Secs. 9, 11, 15 & 16. Land, gently rolling. Soil, good 2nd rate.
40.00	North boundary between Secs. 9 & 10. Set a post for quarter section corner, drove a charred stake and raised a mound of earth with trench and pits, as per instructions.
80.00	Set a post for corner to Secs. 3, 4, 9 & 10. Drove a charred stake and raised mound of earth, with trench and pits, as per instructions. Land, gently rolling prairie. Soil, good 2nd rate.