

Subdivisions, T. 3 N., R. 30 E.

Chains	
79.80	The post corners to Secs. 20, 21, 28 & 29. Land, rolling prairie. Soil, good 2nd rate.
<hr/> North between Secs. 20 & 21.	
40.00	Set a post for quarter section corner. Drove charred stake and raised mound of earth with trench and pits, as per instructions.
80.00	Set a post for corner to Secs. 16, 17, 20 & 21. Drove a charred stake and raised a mound of earth, with trench and pits, as per instructions. Land has a slight descent to the North, gently rolling prairie. Soil, good 2nd rate.
<hr/> East on a random line between Sections 16 & 21.	
<p style="text-align: right;">Variation 20° 00' East.</p>	
40.00	Set a temporary quarter sec. post.
79.09	Intersect corner to Sections 15, 16, 21 & 22 at post. West on a true line between Secs. 16 & 21.
39.54 $\frac{1}{2}$	Set a post for quarter section corner. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.
79.09	The post corner to Sections 16, 17, 20 & 21. Land, rolling prairie. Soil, good, 2nd rate.
<hr/> North, between Secs. 16 & 17.	
40.00	Set a post for quarter section corner, drove a charred stake and raised mound of earth with trench & pits, as per instructions.
42.50	Indian Trail, course NE & SW.
80.00	Set a post for corner to Secs. 8, 9, 16 & 17. Drove a charred stake and raised mound of earth, with trench and pits, as per instructions.