

Subdivisions, T. 3 N., R. 30 E.

Chains	
89.00	Intersect West boundary of Township, 49 links North of post, corner secs. 19 & 30.
	N. 89° 39' E. on a true line between secs. 19 & 30.
49.00	Set a post for quarter section corner. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.
89.00	The post corner to secs. 19, 20, 29 & 30. Land, gently rolling prairie. Soil, good, 2nd rate.
<hr/>	
	North between Secs. 19 & 20.
27.00	To wagon road and trail, runs NW & SE.
40.00	Set a post for quarter sec. corner. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.
80.00	Set a post for corner to Secs. 17, 18, 19 & 20. Drove charred stake and raised a mound of earth with trench and pits, as per instructions. Land, gently rolling prairie. Soil, good, 2nd rate.
October 24th, 1860.	
<hr/>	
	East on a random line between Secs. 17 & 20.
	Variation 20° 45' East.
40.00	Set a temporary quarter section post.
80.06	Intersect N & S line, 20 links North of corner to Secs. 16, 17, 20 & 21.
	N. 89° 51' W. on a true line between sections 17 & 20.
40.03	Set a post for quarter section corner, drove a charred stake & raised a mound of earth, with trench and pits, as per instructions.
80.06	The post corner to secs. 17, 18, 19 & 20. Land, level prairie.