

Exterior boundary lines of Township No. 3, North of Range No. 31, East of the Willamette Meridian in the State of Oregon. Surveyed by D. S. Payne, Deputy Surveyor, contract No. 100, Dated August 1, 1861

East Boundary.

Chains

August 20, 1861

Having previously adjusted my compass to the course of the Guide Meridian by actual tracing of the West boundary of Township 3, North Range 31 East.

Began at the South East corner of section 36, T. 3 N., R. 31 E.

Var. 19°30' E.

Run Thence North on East boundary of Range 31

31.40 Road to Walla Walla, N. E. & S. W.

40.00 Set charred stake with mound, trench & pits as per insts. for 1/4 section corner.

80.00 Set charred stake with mound, trench and pits as per insts. for corner to Secs. 25 & 36 T. 3 N., R. 31 E., and Secs. 30 & 31, T. 3 N., R. 32 E.

Var. 20°15' E.

Land, level.

Soil, first rate.

North on East boundary section 25, T. 3 N., R. 31 E.

40.00 Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

80.00 Set charred stake with mound, trench and pits as per insts. for corner to Secs. 24 & 25, T. 3 N., R. 31 E. & Secs. 19 & 30, T. 3 N., R. 32 E.

Var. 19°50' E.

Soil, good.

North on East line Section 24

40.00 Set charred stake with mound, trench and pits as per insts. for 1/4 sec. corner.

80.00 Set charred stake with mound, trench and pits as per insts. for corner to secs. 13 & 24, T. 3 N., R. 31 E. and Secs. 18 & 19, T. 3 N., R. 32 E.

Var. 20°15' E.

Land, mostly level.

Soil, 1st rate.