

Subdivision Lines Township No. 3 N., R. 31 E. W. M.

Chains	insts. for qr. sec. corner.
80.22	Corner to Secs. 13 & 14, 23 & 24.
	North on line between 13 & 14.
40.00	Set charred stake with mound, trench and pits as per insts. for qr. sec. corner.
80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 11 & 12, 13 & 14. Var. 20°30' E.
	Land, uneven.
	Soil, sandy, 3rd rate.
	S. 89°18' E. on random between Secs. 12 & 13.
40.00	Set temp. qr. sec. post.
80.36	Intersect Town line 41 links North of corner to Secs. 12 & 13.
	N. 89° W. on true line between Secs. 12 & 13.
40.18	Set charred stake with mound, trench and pits as per insts. for qr. sec. corner.
80.36	Corner to Secs. 11 & 12, 13 & 14. Soil, 2nd rate.
	August 26
	North on line between Secs. 11 & 12.
27.00	Ravine N. 60° W.
40.00	Set charred stake with mound, trench and pits as per insts. for qr. sec. corner.
80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 1 & 2, 11 & 12. Var. 20°36' E.
	Surface, uneven.
	Soil, 2nd rate.
	S. 89°18' E. on random between Secs. 1 & 12.
40.00	Set Temp. qr. sec. post.
80.30	Intersect Town. line 28 lks. North of corner to Secs. 1 & 12.
	N. 89°06' W. on true line between Secs. 1 & 12.