

Subdivision Lines Township No. 3 N., R. 31 E. W. M.

Chains	<p>insts. for corner to Sections 10, 11, 14 & 15. Var. 19°30' E.</p>
	<p>S. 89°18' E. on random between Secs. 11 & 14.</p>
40.00	Set Temporary $\frac{1}{4}$ sec. post.
79.84	Intersect section line at corner to sections 11 & 12, 13 & 14.
	N. 89°18' W. on true line between sections 11 & 14.
39.92	Set charred stake with mound, trench and pits as per instructions for $\frac{1}{4}$ section corner.
79.84	Corner to Sections 10 & 11, 14 & 15. Land, level. Soil, 2nd rate.
	North on true line between Secs. 10 & 11.
40.00	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
61.00	Ravine N. 60° W.
80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 2, 3, 10 & 11. Var. 18°35' E.
	S. 89°18' E. on random between Secs. 2 & 11.
40.00	Set temp. $\frac{1}{4}$ sec. post.
80.10	Intersect section line 24 lks. North of corner to secs. 1, 2, 11 & 12.
	N. 89°08' W. on true line between Secs. 2 & 11.
40.05	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
80.10	Corner to Secs. 2 & 3, 10 & 11. Some sand, Soil, 2nd rate.
	North on random between Sections 2 & 3.
40.00	Set temp. $\frac{1}{4}$ sec. post.
79.40	Intersect Town. line 45 lks. West of post.
	S. 20' W. on true line between Secs. 2 & 3.
39.40	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner