

Subdivision Lines Township 3 N., R. 31 E. W. M.

Chains	
40.00	Set charred stake with mound, trench & pits as per insts. for $\frac{1}{4}$ sec. corner.
80.00	Corner to Secs. 21, 22, 27 & 28. Surface, uneven. Soil, 2nd rate.
North on line between Secs. 21 & 22.	
40.00	Set charred stake with mound, trench and pits as per insts. for qr. section corner.
53.00	Ravine N. 45° W.
80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 15 & 16, 21 & 22. Var, 19°40' E. Soil, 2nd rate. Sandy in ravine.
S. 89°18' E. on random between Secs. 15 & 22.	
40.00	Set Temp. $\frac{1}{4}$ sec. post.
79.76	Intersect section line 30 links south of corner to Secs. 14 & 15, 22 & 23. N. 89°30' W. on true line between Secs. 15 & 22.
39.88	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
79.76	Corner to 15 & 16, 21 & 22. Soil, 2nd rate.
North on line between Secs. 15 & 16.	
40.00	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 9 & 10, 15 & 16. Var. 19°54' E. Soil, good.
S. 89°18' E. on random between Secs. 10 & 15.	
40.00	Set Temp. $\frac{1}{4}$ sec. post.
79.84	Intersect section line 30 lks. South of corner to Secs. 10 & 11, 14 & 15.