

Subdivision Lines Township 3 N., R. 31 E. W. M.

Chains	N. 89°30' W. on true line between Secs. 10 & 15.
39.92	Set charred stake with mound, trench, and pits as per instrs. for $\frac{1}{4}$ sec. corner.
79.84	Corner to Secs. 9 & 10, 15 & 16. Land, rolling. Soil, 2nd rate.
	North on line between Secs. 9 & 10.
40.00	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
80.00	Set charred stake with mound, trench and pits as per instructions for corner to sections 3 & 4, 9 & 10. Var. 19°30' E. Soil, 2nd rate.
	S. 89°18' E. on random between Secs. 3 & 10.
40.00	Set Temp $\frac{1}{4}$.sec. post.
79.92	Intersect section line 74 lks. South of corner to Secs. 2 & 3, 10 & 11. N. 89°30' W. on true line between Secs. 3 & 10.
39.96	Set charred stake with mound, trench and pits as per instrs. for $\frac{1}{4}$ sec. corner.
79.92	Corner to Secs. 3 & 4, 9 & 10. Soil somewhat sandy. Soil, 2nd rate.
	North on random between Secs. 3 & 4.
40.00	Set Temp. $\frac{1}{4}$ sec. post.
80.12	Intersect town line at post corner to Secs. 3 & 4. South on true line between Secs. 3 & 4.
40.12	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
80.12	Corner to Secs. 3 & 4, 9 & 10. Land, uneven. Soil, 2nd rate.
	August 29 Var. 20° E. North on line between Secs. 32 & 33.