

Subdivision Lines Township 3 N., R. 31 E. W. M.

| | |
|--------|--|
| Chains | North on line between Secs. 20 & 21. |
| 40.00 | Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner. |
| 80.00 | Set charred stake with mound, trench and pits as per insts. for corner to Secs. 16 & 17, 20 & 21. Var. 20°50' E. Soil, 2nd rate. |
| | S. 89°18' E. on random between Secs. 16 & 21. |
| 40.00 | Set Temp. $\frac{1}{4}$ sec. post. |
| 80.00 | Intersect sec. line 80 links North of corner to Secs. 15 & 16, 21 & 22. N. 88°45' W. on true line between Secs. 16 & 21. |
| 14.00 | Ravine N. 45° W. |
| 40.00 | Set charred stake with mound, trench & pits as per instrs. for $\frac{1}{4}$ sec. corner. |
| 80.00 | Corner to sec. 16 & 17, 20 & 21. Bottom of ravine sandy. Soil, 2nd rate. |
| | North on line between Secs. 16 & 17. |
| 14.00 | Ravine N. 45° W. |
| 40.00 | Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner. |
| 80.00 | Set charred stake with mound, trench and pits as per instrs. for corner to Secs. 8 & 9, 16 & 17. Var. 20° E. Soil, 2nd rate. |
| | S. 89°18' E. on random between Sec. 9 & 16. |
| 40.00 | Set Temp. stake for $\frac{1}{4}$ sec. corner. |
| 80.00 | Intersect section line 60 lks. north of corner to Secs. 9 & 10, 15 & 16. N. 88°52' W. on true line between Secs. 9 & 16. |
| 40.00 | Set charred stake with mound, trench and pits as per instrs. for $\frac{1}{4}$ sec. corner. |
| 80.00 | Corner to Secs. 8 & 9, 16 & 17. Some sand. Soil, 3rd rate. |