

Subdivision Lines of Township 3 North, Range 32 E. W. M.

Chains	
40.60	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
80.60	The corner to Secs. 1, 2, 11 & 12. Land, gently rolling. Soil, 1st rate. October 25th 1864
North between Secs. 34 & 35.	
40.00	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
61.50	Umatilla & Walla Walla Road bears NE. & S.W.
80.00	Set post for corner to Secs 34, 35, 26 & 27 in mound of Earth with charred stake, pits &c as per instructions. Land, rolling. Soil, 2nd rate.
East on a random line between Secs. 26 & 35.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. cor.
79.80	Intersect N. & S. line 35 lks. North of corner to Secs. 25, 26, 35 & 36 from which I run N. 89°45' W. on a true line between Secs. 26 & 35.
39.90	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
69.00	Walla Walla & Umatilla Road bears N.E. & S.W.
79.80	The corner to Secs. 26, 27, 34 & 35. Land, level. Soil, 1st rate.
North between Secs. 26 & 27.	
Var. 20 $\frac{1}{4}$ ° E.	
40.00	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 22, 23, 26 & 27 in mound of Earth with charred stake, pits &c as per instructions. Land, level grass plain. Soil, 1st rate.