

Subdivision Lines of Township 3 North, Range 32 E., W.M.

Chains

- East on a random line between Secs. 23 & 26.
- 40.00 Set post for temporary  $\frac{1}{4}$  Sec. cor.
- 79.80 Intersect N. & S. line at corner to Secs. 23, 24, 25 & 26 from which corner I run West on a true line between Secs. 23 & 26.
- 39.90 Set post for  $\frac{1}{4}$  sec. corner in mound of Earth with charred stake, pits &c as per instructions.
- 79.80 The corner to Secs. 22, 23, 26 & 27.  
Land, gently rolling.  
Soil, 2nd rate.
- 
- North between Secs. 22 & 23.  
Var.  $20\frac{1}{2}^{\circ}$  E.
- 40.00 Set post for  $\frac{1}{4}$  Sec. corner in mound of Earth with charred stake, pits, &c as per instructions.
- 80.00 Set post for corner to Secs. 14, 15, 22 & 23 in mound of Earth with charred stake, pits &c as per instructions.  
Land, level grass plain.  
Soil, 1st rate.
- 
- East on a random line between Secs. 14 & 23.
- 40.00 Set temporary  $\frac{1}{4}$  Sec. Cor.
- 79.75 Intersect N. & S. line at corner to Secs. 13, 14, 23 & 24 from which I run West on true line between Secs. 14 & 23.
- 39.88 Set post for  $\frac{1}{4}$  Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
- 79.75 The corner to Secs. 14, 15, 22 & 23.  
Land, gently rolling.  
Soil, 1st rate.
- 
- North between Secs. 14 & 15.  
Var.  $20^{\circ}$  E.
- 40.00 Set post for  $\frac{1}{4}$  Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
- 64.50 Ravine bears West.