

Subdivision Lines of Township 3 North, Range 32 E. W. M.

Chains	<p>North on a random line between Secs. 3 & 4. Var. 20° E.</p>
40.00	Set post for temporary $\frac{1}{4}$ Sec. cor.
80.60	<p>Intersect North boundary 37 lks. West of corner to Secs. 3 & 4 from which I run S. 0°16' W. on a true line be- tween Secs. 3 & 4.</p>
40.60	<p>Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.</p>
80.60	<p>The corner to Secs. 3, 4, 9 & 10. Land, gently rolling. Soil, good 2nd rate. October 27th 1864.</p>
<p>North between Secs. 32 & 33.</p>	
40.00	Set stone 12x8x6 for $\frac{1}{4}$ sec. cor.
80.00	<p>Set post for corner to Secs. 28, 29, 32 & 33 in mound of earth with charred stake, pits &c as per instructions Land, rolling. Soil, 2nd rate.</p>
<p>East on a random line between Secs. 28 & 33.</p>	
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
80.14	<p>Intersect N. & S. line at corner to Secs. 27, 28, 33 & 34 from which I run West on a true line between Secs. 28 & 33.</p>
40.07	<p>Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.</p>
80.14	<p>The corner to Secs. 28, 29, 32 & 33. Land, gently rolling. Soil, good 2nd rate.</p>
<p>North between Secs. 28 & 29. Var. 20° E.</p>	
40.00	<p>Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.</p>
80.00	<p>Set post for corner to Secs. 20, 21, 28 & 29 in mound of Earth with charred stake, pits &c as per instructions.</p>