

Subdivision Lines of Township 3 North, Range 32 E. W. M.

Chains	
45.50	Ravine bears West.
80.00	Set post for corner to Secs. 8, 9, 16 & 17 in mound of Earth with charred stake, pits &c as per instructions. Land, gently rolling. Soil, 2nd rate.
	East on a random line between Secs. 16 & 9.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.20	Intersect N. & S. line at corner To Secs. 9, 10, 15 & 16 from which corner I run West on a true line between Secs. 9 & 16.
40.10	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
80.20	The corner to Secs. 8, 9, 16 & 17. Land, gently rolling. Soil, 2nd rate
	North between Secs. 8 & 9. Var. 20° E.
40.00	Set stone 18x10x6 for $\frac{1}{4}$ Sec. cor.
80.00	Set post for corner to Secs. 4, 5, 8 & 9 in mound of Earth with charred stake, pits &c as per instructions. Land, gently rolling. Soil, 2nd rate.
	East on a random line between Secs. 4 & 9.
40.00	Set post for temporary $\frac{1}{4}$ Sec. cor.
79.80	Intersect N & S. line at corner to Secs. 3, 4, 9 & 10 from which corner I run West on a true line between Secs. 4 & 9.
39.90	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
79.80	The corner to Secs. 4, 5, 8 & 9. Land, gently rolling. Soil, good 2nd rate.
	North on a random line between Secs. 4 & 5. Var. 19 $\frac{1}{2}$ ° E.