

Subdivision Lines of Township 3 North, Range 32 E. W. M.

Chains	
40.00	Set post for temporary $\frac{1}{4}$ Sec. cor.
80.68	Intersect North boundary at corner to Secs. 4 & 5 from which corner I run South on a true line between Secs. 4 & 5.
40.68	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
80.68	The corner to Secs. 4, 5, 8 & 9. Land, gently rolling. Soil, good 2nd rate.
<hr/>	
	North between Secs. 31 & 32.
.10	Old Emigrant Road bears NW & SE.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 29, 30, 31 & 32 in mound of Earth with charred stake, pits &c as per instructions. Land, level. Soil, 2nd rate.
<hr/>	
	East on a random line between Secs. 29 & 32.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersect N. & S. line 35 lks. South of corner to Secs. 28, 29, 32 & 33 from which I run S. 89°45' W. on a true line between Secs. 29 & 32. .
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
80.00	The corner to Secs. 29, 30, 31 & 32. Land, level. Soil, 2nd rate
<hr/>	
	West on a random line between Secs. 30 & 31.
40.00	Set post for temporary $\frac{1}{4}$ Sec. cor.
86.00	Intersect West boundary at corner to Secs. 30 & 31 from which I run East on a true line between Secs. 20 & 31.
46.00	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
86.00	The corner to Secs. 29, 30, 31 & 32.

October 28th 1864