

Subdivision Lines of Township 3 North, Range 32 E. W. M.

Chains	Land, level. Soil, 2nd rate.
North between Secs. 29 & 30. <div style="text-align: right;">Var. 20$\frac{1}{4}$° E.</div>	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 19, 20, 29 & 30 in mound of Earth with charred stake, pits &c as per instructions. Land, rolling. Soil, 2nd rate.
East on a random line between Secs. 20 & 29.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. cor.
80.40	Intersect N. & S. line 30 lks. South of corner to Secs. 20, 21, 28 & 29 from which I run S. 89°47' W. on a true line between Secs. 20 & 29.
40.20	Set Stone 15x12x10 for $\frac{1}{4}$ Sec. cor.
80.40	The corner to Secs. 19, 20, 29 & 30. Land, level. Soil, 2nd rate.
West on a random line between Secs. 19 & 30.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. cor.
85.30	Intersect West boundary 35 lks. South of corner to Secs. 19 & 30 from which I run S. 89°45' E. on a true line between Secs. 19 & 30.
45.30	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
85.30	The corner to Secs. 19, 20, 29 & 30. Land, level. Soil, 2nd rate.
North between Secs. 19 & 20. <div style="text-align: right;">Var. 20° E.</div>	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.