

Subdivisions of Township 3 North, Range 33 E. W. M.

Chains	
80.00	Set stone 24x5x5 for corner to Secs. 13, 14, 23 & 24. Land, level. Soil, good 2nd rate.
	East on a random line between Secs. 13 & 24.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
79.20	Intersect East boundary 68 lks. North of corner to secs. 13 & 24 from which I run N. 89°31' W. on a true line between Secs. 13 & 24.
39.60	Set stone 26x12x4 for $\frac{1}{4}$ sec. corner.
55.00	Dry bed of creek, course S.W.
79.20	The corner to Secs. 13, 14, 23 & 24. Land, gently rolling. Soil, 2nd rate.
	North between Secs. 13 & 14. Var. 18° E.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 11, 12, 13 & 14 in mound of earth with charred stake, pits &c as per instructions. Land, level. Soil, 2nd rate.
	East on a random line between Secs. 12 & 13.
40.00	Set post for temporary $\frac{1}{4}$ sec. corner.
79.08	Intersect at East boundary 48 lks. north of corner to Secs. 12 & 13 from which I run N. 89°40' W. on a true line between Secs. 12 & 13.
39.54	Set post for $\frac{1}{4}$ Sec. cor. in mound of earth with charred stake, pits &c as per instructions.
79.08	The corner to Secs. 11, 12, 13 & 14. Land, rolling. Soil, good 2nd rate.
	North between Secs. 11 & 12. Var. 19° E.