

Subdivisions of Township 3 North, Range 33 E. W. M.

Chains	Land, level. Soil, 1st rate.
	North between Secs. 9 & 10. Var. 20° E.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
60.30	Umatilla & Walla Walla road bears NE. & SW.
80.00	Set post for corner to Secs. 3, 4, 9 & 10 in mound of earth with charred stake, pits &c as per instructions.
	Land, level. Soil, 1st rate.
	East on a random line between Secs. 3 & 10.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
79.89	Intersect N. & S. line at cor. to Secs. 2, 3, 10 & 11 from which corner I run West on a true line bet. Secs. 3 & 10.
24.60	Umatilla & Walla Walla road bears NE. & SW.
39.95	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
79.89	The corner to Secs. 3, 4, 9 & 10.
	Land, rolling. Soil, 1st rate.
	North on a random line between Secs. 3 & 4. Var. 20° E.
40.00	Set posts for temporary $\frac{1}{4}$ sec. cor.
80.45	Intersect North boundary 90 lks. East of corner to Secs. 3 & 4, from which I run S.0°39' E. on a true line bet. Secs. 3 & 4.
40.45	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.45	The corner to Secs. 3, 4, 9 & 10.
	Land, rolling. Soil, 1st rate.
	North between Secs. 32 & 33.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions
80.00	Set stone 22x8x8 for corner to Secs. 28, 29, 32 & 33.