

Subdivisions of Township 3 North, Range 33 East W. M.

Chains	
40.10	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.20	The corner to Secs. 5, 6, 7 & 8. Land, level. Soil, good 2nd rate.
40.00	West on a random line between Secs. 6 & 7. Set temporary $\frac{1}{4}$ sec. corner.
77.10	Intersect West boundary 35 lks. North of corner to Secs. 6 & 7 from which I run N.89°45' E. on a true line between Secs. 6 & 7.
37.10	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
77.10	The corner to Secs. 5, 6, 7 & 8. Land, level. Soil, 1st rate.
40.00	North on a random line between Secs. 5 & 6. Var. 19° E. Set temporary $\frac{1}{4}$ sec. corner.
80.40	Intersect North boundary 70 lks. East of corner to Secs. 5 & 6 from which I run S.0°30' E. on a true line between Secs. 5 & 6.
40.40	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.40	The corner to Secs. 5, 6, 7 & 8. Land, level. Soil, 1st rate. November 11th 1864.
<p style="text-align: center;">General Description</p> <p>The land in this Township is either level or gently rolling. Soil, 1st and 2nd rate, covered with very heavy growth of grass.</p> <p>There are no streams of water, but plenty of excellent springs through the Township.</p> <p>There is but little timber in the Township, though there is some alder and willow in the dry creek that runs</p>	