

Subdivisions of Township 3 North, Range 33 East W. M.

Chains	<p>through the Township. There are about 20 settlers, all in the creek.</p>
<p>Field notes of the Subdivisional lines of Township No. 3 North, Range 33 East of the Will. Mer. by Z. F. Moody, under contract 164, dated Oct. 4, 1871.</p>	
<p>North bet. Secs. 35 &amp; 36.</p>	
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. corner.
80.00	Set post and made earth mound for cor. to Secs. 35, 36, 25, 26.
<p>Land, level. Soil, good.</p>	
<p>East on random bet. Secs. 25 &amp; 36. V. 20° E.</p>	
40.00	Set temporary $\frac{1}{4}$ S. cor.
79.60	Intersected N. & S. line 40 lks. S. of cor. S. 89°43' W. on true line.
39.80	Set post and made earth mound for $\frac{1}{4}$ S. cor.
79.60	To corner.
<p>Land, level. Soil, good.</p>	
<p>North bet. Secs. 25 &amp; 26.</p>	
40.00	Set post and made earth mound for $\frac{1}{4}$ S. cor.
80.00	Set post and made earth mound for cor. to Secs. 25, 26, 23, 24.
<p>Land, level. Good soil.</p>	
<p>East on random bet. Secs. 24 &amp; 25. V. 21° E.</p>	
40.00	Set temporary $\frac{1}{4}$ S. cor.
79.54	Intersected N. & S. line 21 lks. S. of cor. S. 89°51' W. on true line.
39.77	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
79.54	To corner.
<p>Land, rolling.</p>	