

Subdivisions of T. 3 North

Subdivisions of T. 3 North, R. 33 East

Chains 40.00	Set basalt stone 9x8x7 ins. 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face, dug pits 18x18x12 ins. N. and S. of stone, 5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
64.00	Wagon road, course NE.
80.00	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 25, 26, 35 and 36, marked T 3 N S 25 on NE., R 33 E S 36 on SE., S 35 on SW., and S 26 on NW. faces, with 1 notch on S. and E. edges, dug pits 18x18x12 ins. in each sec., 5 $\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, 4 ft. base around post. Land, level. Soil, 1st rate. Not cultivated. No timber. Some grass.
	East on ran. bet. Secs. 25 and 36. Va. 20° East. Set temporary cors. at 20.40 and 60 chs.
78.75	Intersect E. bdy., Township 52 lks. S. of cor. to Secs. 30, 31, 25 and 36. Thence. S. 89°38' W. on true line. Va. 20 $\frac{1}{4}$ ° East.
19.68	Set charred stake 12 ins. in the ground for 1/16 sec. cor., dug pits 18x18x12 ins. E. and W. of cor., 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
39.37	Deposited charred stake 12 ins. in ground for $\frac{1}{4}$ sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground and marked $\frac{1}{4}$ S on N. face.
59.05	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor., dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist., raised md. of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft.