

Subdivisions of T. 3 North, R. 33 East

Chains	Descend.	
67.00	Gulch NW.	-100
80.00	<p>Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 28, 29, 32 and 33, marked T 3 N S 28 on NE., R 33 E S 33 on SE., S 32 on SW., and S 29 on NW faces, with 1 notch on S and 4 notches E. edges, dug pits 18x18x12 ins. in each sec., 5½ ft. dist., raised mound of earth 2 ft. high, 4½ ft. base around it.</p> <p>Land, rolling.</p> <p>Soil, 1st rate. Partly cultivated.</p> <p>No timber. Wheat and grass.</p>	
40.00	<p>East on random bet. Secs. 28 and 33.</p> <p style="text-align: right;">Va. 21° East.</p> <p>Set temporary ¼ sec. cor. and at</p>	
79.60	<p>Intersect N. and S. line 60 lks. N. of cor. to Secs. 27, 28, 33 and 34. Thence</p> <p>N. 89°34' W. on true line.</p> <p style="text-align: right;">Va. 23° East.</p>	
39.80	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S. on N. face.</p>	
79.60	<p>Cor. to Secs. 28, 29, 32 and 33.</p> <p>Land, level.</p> <p>Soil 1st rate. Not cultivated.</p> <p>No timber. Short grass.</p>	
17.00	<p>South on true line bet. Secs. 32 and 33.</p> <p style="text-align: right;">Va. 21° East.</p> <p>Gulch and Wagon road SE.</p>	-50
40.00	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor., dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake 2 ft. long,</p>	