

Examination of Corners of Township 3 North, Range 33 East, by James P. Currin and James E. Noland under their special contract, dated May 4, 1887.

Chains

From corner, Townships 2 & 3 N., R. 33 & 34 Ea., I run North between Secs. 31 & 36 to cor. Secs. 25, 30, 31 & 36; found the old post standing, but badly defaced. Set new post, 4 ft. long by 4 ins. square, 24 ins. in the ground, marked S 30 T e N on NE., S 31 R 34 E on SE.; S 36 R 33 E on SW., & S 25 on NW. faces, with 5 notches on N. & 1 on S. edges. Reset it in earth mound and repaired pits & mound. Pits are  $5\frac{1}{2}$  ft. dist. in each sec. & partly filled.

Cor. to Secs. 19, 24, 25 & 30 I found broken and reset in md. of earth with pits  $5\frac{1}{2}$  ft. dist. in each sec., partly filled. The post is 2 ft. long by 4 ins. square, marked S 19 on NE., S 30 on SE., S 25 on SW., & S 24 on NW. faces. Other marks decayed off. I cut T 3 N on NE., R 34 E on SE & R 33 E on SW. faces, with 4 notches on N. & 1 on S. edges & reset post in md. of earth.

Cor. Secs. 13, 18, 19 & 24, found a post in earth md. 2 ft. above ground, marked S 18 T 3 N on NE., S 19 R 34 E on SE., S 24 R 33 E on SW., & S 13 on NW. faces, with 3 notches on N. & S. edges. Pits  $5\frac{1}{2}$  ft. dist. in each sec., almost filled up, but show plainly. Mound mostly gone

Going North to meander cor. between Secs. 13 & 18. I find a stone 14x8x6 ins. firmly set in the ground, marked U R M C on S. face with a pit 36x36 ins. 8 lks. S. of it. Pit most full. Earth md. about gone, by overflow of creek.

Found cor. Secs 22, 23, 26 & 27 to be a stone 12x10x6 ins. above ground, marked with 2 notches on E. & 2 on S. edges. Pit in each sec.  $5\frac{1}{2}$  ft. dist. in good repair. Earth md. settled down & blown away so as to be around it.

Found meander corner between Secs. 21 & 22, a stone 12x10x10 ins., marked U R M C on S. face. A pit 3 ft. square, 8 lks. North of stone. Pit nearly