

Survey of South Boundary of Township No. 4 North, Range 34 East W. M. in the state of Oregon, by William H. Odell, deputy Surveyor, under contract No. 114, bearing date, July 2nd 1866

Chains

Commenced the survey of the Exterior boundaries of Township, number 4, North of Base Line of Range 34 East of Willamette Meridian, beginning at the North East corner of Township number 3, North of the Base Line of Range 33 East of Willamette Meridian.

July 25th 1866.

East on South boundary of Section 31.

40.00 Set 1/4 section post corner. Drove charred stake, dug pits and raised mound as per instructions.

80.00 Set post corner for Sections 31, 32, 5 & 6. Drove charred stake, dug pits and raised mound as per instructions.

Land, gently rolling prairie. Good grass.

Soil, 2nd rate.

East on South boundary of Section 32.

Var. 21° East.

8.50 Dry gulch, course South West.

-15

40.00 Set 1/4 section post corner. Drove charred stake, dug pits and raised mound as per instructions. 10

80.00 Set post corner for sections 32, 33, 4 & 5. Drove charred stake, dug pits and raised mound as per instructions.

Land, rolling prairie. Good grass.

Soil, 2nd rate.

East on South boundary of Section 33.

Var. 21° East.

40.00 Set 1/4 section post corner, drove charred stake, dug pits and raised mound as per instructions.

80.00 Set post corner for sections 33, 34, 3 & 4. Drove charred stake, dug pits and raised mound as per instrs.

Land, rolling prairie. Good grass.

Soil, 2nd rate.

East on South boundary of Section 34.

Var. 21° East.