

Township 3 North, Range 34 East W. M.

Chains 80.00	<p>Set post corner for sections 2, 3, 10 & 11. Drove charred stake, dug pits and raised mound as per instructions.</p> <p>Land, rolling. Good grass.</p> <p>Soil, 1st rate.</p>
	<p>West between Sections 3 & 10.</p> <p style="text-align: right;">Var. 21° E.</p>
40.00	<p>Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions.</p>
80.00	<p>Set post corner for sections 3, 4, 9 & 10. Drove charred stake, dug pits and raised mound as per instructions.</p> <p>Land, gently rolling. Good grass.</p> <p>Soil, 2nd rate.</p>
	<p>North on random between Sections 3 & 4.</p> <p style="text-align: right;">Var. 21° E.</p>
40.00	<p>Set temporary $\frac{1}{4}$ section corner.</p>
80.25	<p>Intersected East and West line 61 links West of post cor. S. 0°34' E. on true line.</p>
40.25	<p>Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions.</p>
42.25	<p>Wild Horse Creek 10 links wide, course S. 38° W.</p>
80.25	<p>To post corner.</p> <p>Land, gently rolling. Good grass.</p> <p>Soil, 1st rate.</p>
	<p>South between Sections 9 & 10.</p>
40.00	<p>Set post corner for $\frac{1}{4}$ section, drove charred stake, dug pits and raised mound as per instructions.</p>
80.00	<p>Set post corner for Sections 9, 10, 15 & 16. Drove charred stake, dug pits and raised mound as per instructions.</p> <p>Land, gently rolling. Good grass.</p> <p>Soil, 1st rate.</p>