

Township 3 North, Range 34 East W. M.

Chains 40.00	Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions.
80.00	Set post corner for sections 5, 6, 7 & 8. Drove charred stake, dug pits and raised mound as per instructions. Land, rolling. Good grass. Soil, good 2nd rate.
East on random between Sections 5 & 8. Var. 21° E.	
40.00	Set temporary $\frac{1}{4}$ section corner.
79.76	Intersected North and South line 57 links South of post corner S. 89°36' W. on true line.
39.88	Set post for corner for $\frac{1}{4}$ section, drove charred stake, dug pits and raised mound as per instructions.
79.76	To post corner. Land, rolling. Soil, 2nd rate.
West between Sections 6 & 7 on random.	
40.00	Set temporary $\frac{1}{4}$ section corner.
80.23	Intersected North and South line 27 links South of post corner S. 89°48' East on true line.
40.23	Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions.
80.23	To post corner. Land, rolling. Good grass. Soil, 2nd rate.
North between Sections 5 & 6 on random.	
40.00	Set post temporary corner for $\frac{1}{4}$ section.
80.30	Intersected East and West line 59 links East of post cor. S. 00°25' E. on true line.
40.30	Set post corner for $\frac{1}{4}$ section. Drove charred stake, dug pits and raised mound as per instructions.
80.30	To post corner. Land, rolling. Soil, 2nd rate. Well adapted to stock raising, being well