

Subdivisional Lines of Township 3 North, R. 34 E. W. M.

Chains	Soil, good.
	East on random bet. Secs. 3 & 10. V. 21° E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.64	Intersected N. & S. line 14 lks. N. of cor. N. 89°54' W. on true line.
39.82	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
79.64	To cor. Land, rolling. Good soil.
	North bet. Secs. 3 & 4.
39.24	To Wild Horse ck., the boundary of the Reservation.
	West bet. Secs. 4 & 9.
18.40	To Wild Horse ck., the boundary of the Indian Reservation.
	North bet. Secs. 32 & 33.
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.00	Set post and made earth mound for cor. to Secs. 32, 33, 28 & 29. Land, rolling. Soil, good.
	East on random bet. Secs. 28 & 33. V. 20° E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.40	Intersected N. & S. line 14 lks. N. of cor. N. 89°54' W. on true line.
40.20	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.40	To corner. Land, rolling. Soil, good.
	North bet. Secs. 28 & 29.
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.00	Set post and made mound of earth for cor. to Secs. 28, 29, 20, 21. Land, rolling.