

South Boundary of Township 4 North, R. 34 E. W. M.

Chains 80.00	<p>Set a basalt 10x8x7 ins. 6 ins. in the ground for cor. to Secs. 2, 3, 34 &amp; 35. Marked 2 notches on E. &amp; 4 notches on W. edges. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. and raised a mound of earth 2 ft. high, 4½ ft. base along side.</p> <p>Land, level. <span style="float: right;">Some grass.</span></p> <p>Soil, 1st rate. <span style="float: right;">Aug. 17, 1887</span></p>
<p>South 89°54' E. on true line on N. bdy. Sec. 2. Var. 20° East.</p>	
3.50	Wagon Road, course NW.
20.00	<p>Deposited a charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of cor., 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 on N. face.</p>
40.00	<p style="text-align: right;">8 ins.</p> <p>Set a basalt stone 12x10x8 ins./in the ground for ¼ sec. cor., marked ¼ on N. face. Dug pits 18x18x12 ins. E. &amp; W. of cor., 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base along side.</p>
60.00	<p>Deposited a charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of cor., 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 on N. face.</p>
78.80	Enter field.
80.00	<p>Set a post 48x4x4 ins., 12 ins. in the ground for cor. to Secs. 1, 2, 35 &amp; 36, marked R. 34 E. S. 36 on NE., S 1 on SE., T 3 N S 2 on SW., T 4 N S 35 on NW. faces, with 5 notches on W. &amp; 1 notch on E. edges, dug pits 18x18x12 in each sec., 5½ ft. dist., raised a mound of earth 2 ft. high, 4½ ft. base around post.</p> <p>Land, rolling. <span style="float: right;">Some grass.</span></p> <p>Soil, 1st rate.</p>