

Exteriors of Township 3 North, Range 34 E. W. M.

Chains 80.00	<p>Set a post 48x4x4 ins. (in field), 12 ins. in the ground for cor. to Secs. 30, 31, 25 &amp; 36, marked R. 35 E S 30 on NE., S 31 on SE., R 34 E S 36 on SW., T 3 N S 25 on NW., with 5 notches on N. &amp; 1 notch on S. edges.</p> <p>Dug pits 18x18x12 ins. in each sec., 5½ ft. dist., raised a mound of earth 2 ft. high, 4½ ft. base around post.</p> <p>Land, nearly level.                      Good grass.</p> <p>Soil, 1st rate.</p>
	<p>South on E. bdy. of Sec. 36.</p> <p style="text-align: center;">Var. 20° E.</p>
13.30	Fence & leave field.
20.00	Set a post 36x3x3 ins., 12 ins. in the ground for 1/16 sec. cor., marked 1/16 S on W. face. Dug pits 18x18x12 ins. N. & S. of post, 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base around post.
22.50	Wagon road, course E. & W.
24.00	Wagon road, course SE. & NW.
40.00	Set a post 36x3x3 ins., 12 ins. in the ground for ¼ sec. cor., marked ¼ S on W. face. Dug pits 18x18x12 ins. N. & S. of cor., 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base around post.
51.50	Gulch, course W.
60.00	Set a post 36x3x3 ins., 12 ins. in the ground for ¼ sec. cor., marked 1/16 S on W. face. Dug pits 18x18x12 ins. N. & S. of cor., 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base around post.
80.00	Set a basalt stone 16x12x12 ins. 10 ins. in the ground for cor. to Tps. 3 N., Rs. 34 & 35 E., marked 6 notches on NE. & W. edges, raised a mound of stone around it.
	<p>Pits impracticable.</p> <p>Land, rolling.                                      Some grass.</p> <p>Soil, 1st rate.</p>