

Survey of the Subdivisional lines of Township 3 North, Range 34 East W. M. by James P. Currin and James E. Noland, U. S. Deputy Surveyors under their special contract, dated May 4th, 1887.

Chains	By permission granted in the special instructions on this work and owing to the peculiar location of the fractional allotings on the NW. boundary of the work to be done in this township, I commence at the cor. to Secs. 1 and 2, T. 3 N., R. 34 E. and 35 and 36 T. 4 N., R. 34 E. and Run South on true line bet. Secs. 1 & 2.
	Va. 21°15' East.
	Ascend sloping hill.
3.00	Leave garden, E. and W.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
32.10	Fence E. and W.
39.50	Fence E. and W.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S. on W. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on W. face.
78.50	Lane, E. and W.
80.00	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 1, 2, 11 and 12, marked T 3 N S 1 on NE., R 34 E S 12 on SE., S 11 on SW. and S 2 NW. faces with 5 notches on S and 1 notch on E. edges. Dug pits 18x18x12 ins. in each sec. 5½ ft. dist. Raised mound of earth 2 ft. high, 4½ ft. base around