

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	<p>ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked <math>\frac{1}{4}</math> S on N. face.</p>
59.55	<p>Gradually descend.</p> <p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{16}</math> sec. cor. Dug pits <math>18 \times 18 \times 12</math> ins. E. and W. of stake, <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked <math>\frac{1}{16}</math> S on N. face.</p>
79.40	<p>Cor. to Secs. 13, 14, 23 and 24.</p> <p>Land, gently rolling and high.</p> <p>Soil, 1st rate. Mostly cultivated.</p>
<p>South bet. Secs. 23 and 24.</p> <p style="text-align: center;">Va. <math>21^\circ</math> East.</p>	
4.60	<p>Fence and enter field E. and W.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground, Dug pits <math>18 \times 18 \times 12</math> ins. N. and S. of stake, <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked <math>\frac{1}{16}</math> S on W. face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> sec. cor. Dug pits <math>18 \times 18 \times 12</math> ins. N. and S. of cor. <math>5\frac{1}{2}</math> ft. dist. Raised mound of stone and earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it, and in N. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked <math>\frac{1}{4}</math> S on W. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{16}</math> sec. cor. Dug pits <math>18 \times 18 \times 12</math> ins. N. and S. of stake, <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked <math>\frac{1}{16}</math> S on W. face.</p>
80.00	<p>Set post 4 ft. long, 4 ins. square, 24. ins. in the ground</p>