

Subdivisions of T. 3 North, R. 34 East W. M.

|  |  |      |
|--|--|------|
| Chains                                     | high, 3½ ft. base over it.   |      |
| 60.07                                      | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of cor., 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.                         | +400 |
| 80.07                                      | Cor. to Secs. 25, 26, 35 and 36<br>Line over breakes N. side of river.<br>Soil, 1st rate on N. ½ and rocky on S ½ mile.  | +600 |
| South bet. Secs. 2 and 3.<br>Va. 20° East. |  |      |
| 1.50                                       | Wagon road, E. and West.   |      |
| 9.30                                       | Fence, NE. and SW.   |      |
| 20.00                                      | Deposited charred stake 12 in. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.                        |      |
| 40.00                                      | Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on W. face.                              |      |
| 44.00                                      | Dry bed of creek, NW.  |      |
| 51.80                                      | Fence, E. and W.   |      |
| 60.00                                      | Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face. Ascend sloping ridge. |      |
| 80.00                                      | Set post 4 ft. long, 4 ins. square, 24 ins. in the ground  |      |