

Subdivisions of T. 3 North, R. 34 East W. M.

Chains 48.60	Wagon road, NE.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
65.75	Enter field E. and W.
80.00	Set stone 14x10x6 ins. 10 ins. in the ground for cor. to Secs. 22, 23, 26 and 27, marked with 2 notches on S. and E. edges. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. and raised mound of earth 2 ft. high, 4½ ft. base over stone
	Land, rolling.
	Soil, 1st rate. Partly cultivated.
East on ran. bet. Secs. 23 and 26.	
Va. 20½° East.	
80.44	Set temporary cors. at 20, 40 and 60 chains, and at Intersect N. and S. line 14 lks. S of cor. to Secs. 23, 24, 25 and 26. Thence S.89°54' West on true line.
Va. 20½° East.	
15.45	Enter field, N. and S.
20.11	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
40.22	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.