

## Subdivisions of T. 3 North, R. 34 East W. M.

Chains 60.33	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 sec. cor., marked 1/16 S on N. face. Dug pits 18x18x12 ins. E. and W. of post, 15½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base around it.
74.56	Partition fence, N. and S.
80.44	Cor. to Secs. 22, 23, 26 and 27. Land, level. Soil, 1st rate. Mostly cultivated.  Aug. 18, 1887.
	South bet. Secs. 26 and 27.  Va. 20¼° East.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
40.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for ¼ sec. cor., marked ¼ S on W. face. Dug pits 18x18x12 ins. N. and S. of post, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base around it.
59.37	Leave field, E. and W.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake, 2 ft. long, sq., 12 ins. 2 ins./in the ground, marked 1/16 S on West face.
80.00	Deposited charred stake 12 ins. in the ground for cor. to Secs. 26, 27, 34 and 35. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist., raised mound of earth 2 ft. high, 4½ ft. base over it and in SE. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked T 3 N S 26 on NE., R 34 E S 35 on SE., S 34 on SW., and S 27 on NW. faces, with 1 notch on