

Subdivisions of T. 3 North, R. 34 East W. M.

Chains 79.80	Intersect S. bdy., Township 20 lks. East of cor. to Secs. 34 and 35. Thence N. 9' E. on true line. Va. 21° East.
12.88	Enter Indians field E. and W.
19.80	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on West face. 400
31.80	Leave field, E. and W.
39.80	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S. on W. face.
52.75	Wagon road, SW.
59.80	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on West face.
79.80	Cor. to Secs. 26, 27, 34 and 35. Land, rolling. Soil, generally, 1st rate. Partly cultivated.
	South bet. Secs. 3 and 4. Va. 21° East. Commencing at what is claimed to be cor. to Secs. 3, 4, 33 and 34, which is stone 8x10x10, buried in the ground by old settlers living in this vicinity. Old post having disappeared.
40.00	Not finding old cor. I set post 3 ft. long, 3 ins. square, 24 ins. in the ground for ¼ sec. cor. Dug pits 18x18x-