

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	Soil, 1st rate. Not under cultivation.
	<p>East on random bet. Secs. 17 and 20.</p> <p style="text-align: center;">Va. 20° East.</p>
40.00	Set temporary $\frac{1}{4}$ sec. corners and at
79.58	Intersect N. and S. line 23 lks. N. of cor. to Secs. 16, 17, 20 and 21. Thence
	N. 89° 50' West on true line.
	Va. 21° East.
39.79	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in ground, marked $\frac{1}{4}$ S on N. face.
72.50	Wagon road, N.
77.30	Wagon road, NE.
79.58	Cor to Secs. 17, 18, 19 and 20.
	Land, level.
	Soil, 1st rate, sandy. Not cultivated but good farming land.
	<p>West on random bet. Secs. 18 and 19.</p> <p style="text-align: center;">Va. 20° East.</p>
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at
75.05	Intersect W. bdy. Township, 90 lks. S. of cor. to Secs. 18, 19, 13 and 24. Thence
	S. 89°19' East on true line.
	Va. 21°30' East.
13.75	Wagon road, NE.
35.05	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. and dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face.