

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	
66.75	Wagon road, NE.
74.75	Cor. to Secs. 19, 20, 29 and 30.
	Land, level. Soil, 1st rate. Not cultivated.
	South bet. Secs. 29 & 30.
	Va. 20° East.
20.00	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. N. & S. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on W. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. N. and S. of stake, 5½ dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
80.00	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to Secs. 29, 30, 31 and 32, marked T 3 N S 29 on NE., R 34 E S 32 on SE., S 31, SW., and S 30 on NW. faces, with 1 notch on S. and 5 notches on E. edges. Dug pits 18x18x12 ins. in each sec., 5½ ft. dist. Raised mound of earth 2 ft. high, 4½ ft. base around it.
	Land, level.