

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	Soil, 1st rate, sandy loam. Uncultivated, but well adapted to farming.
80.20	<p>East on ran. bet. Secs. 29 and 32. Va. 20° East.</p> <p>Set temporary cors. at 20, 40 and 60 chains, and at Intersect. N. and S. line 12 lks. N. of the corner to Secs. 28, 29, 32 and 33. Thence N. 89° 55' W. on true line. Va. same.</p>
12.75	Wagon road, NW.
20.05	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
40.10	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.</p>
60.15	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
80.20	<p>Cor. to Secs. 29, 30, 31 and 32. Land, level. Soil, 1st rate. Not cultivated.</p>
74.65	<p>West on random bet. Secs. 30 and 31. Va. 20° East.</p> <p>Set temporary cors. at 20, 40 and 60 chains, and at Intersect W. bdy. Township 104 lks. S of cor. to Secs.</p>