

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	25, 36, 30 and 31. Thence
	S. 89°12' E. on true line.
	Va. 20 $\frac{1}{4}$ ° East.
2.35	Wagon road, NE.
14.65	Deposited charred stake 12 ins. in the ground for 1/16
	sec. cor. Dug pits 18x18x12 ins. E. and W. of stake,
	5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$
	ft. base over it, and in E. pit, drove stake, 2 ft.
	long, 2 ins. square, 12 ins. in the ground, marked
	1/16 S on N. face.
34.65	Deposited charred stake, 12 ins. in the ground for $\frac{1}{4}$
	sec. cor. Dug pits 18x18x12 ins. E. and W. of stake,
	5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high,
	3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft.
	long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$
	S on N. face.
54.65	Deposited charred stake 12 ins. in the ground for 1/16
	sec. cor. Dug pits 18x18x12 ins. E. and W. of stake,
	5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$
	ft. base over it, and in E. pit drove stake, 2 ft.
	long, 2 ins. square, 12 ins. in the ground, marked
	1/16 S on N. face.
74.65	Cor. to Secs. 29, 30, 31 and 32.
	Land, level.
	Soil, 1st rate. Not cultivated but well adapted to
	farming. Grass short.
	South on random bet. Secs. 31 and 32.
	Va. 20° East
	Set temporary cors. at 20, 40 and 60 chains, and at
79.00	Intersect S. bdy., Township 10 lks. E. of cor. to Secs.
	31 and 32. Thence
	N. 4' East on true line.
	Va. 20° E.
19.00	Deposited charred stake 12 ins. in the ground for 1/16
	sec. cor. Dug pits 18x18x12 ins. N. and S. of stake,