

Subdivisions of T. 3 North, R. 34 East W. M.

Chains	N.89°46' West on true line.	
4.50	Gulch, course S.	-50
19.94	Set basalt stone 14x10x6 ins. 9 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face, and raised mound of earth and stone 2 ft. high, 3½ ft. base around it.	
21.55	Gulch, course S.	-50
39.88	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.	
59.82	Set basalt stone 36x20x8 ins. firmly in the ground for 1/16 sec. cor., marked 1/16 S on N. face, and raised mound of earth and stone 2 ft. high, 4½ ft. base over it.	
79.75	To point of beginning. Land, rolling. Soil, 2nd rate, rocky. Good grass.	
<hr/> <p>East on random through center of sec. 36. Va. 20½° East.</p>		
79.60	Commencing at ¼ sec. cor. bet. Secs. 35 and 36. Set temporary cors. at 20, 40 and 60 chains, and at Intersect E. bdy. 42 lks. N. of ¼ sec. cor. Thence N.89°42' West on true line.	
19.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.	
24.90	Gulch, course S.	-20
39.80	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½	