

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
59.52	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
79.35	<p>To point of beginning. Soil, 1st rate. Land, level. Partly cultivated.</p>
<p>East on random through S. ½ of Sec. 24. Va. 20° East. Commencing at 1/16 sec. cor., 20 chains N. of SW. cor. of Secs. 24 at 20, 40 and 60 chains, and at</p>	
79.40	<p>Intersect E. bdy. 70 lks. N. of 1/16 sec. cor. Thence N.89°30' W. on true line.</p>
19.85	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
39.70	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
59.55	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in East pit drove stake,</p>