

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>Dug pits 18x18x12 ins. E. and W. of post, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base around post.</p>
79.64	<p>To point of beginning. Land, level. Soil, 1st rate. All cultivated.</p>
<p>East on random through Center of Sec. 12. Va. 20½° E.</p>	
79.70	<p>Commencing at ¼ sec. cor. bet. Secs 11 and 12, set temporary cors. at 20, 40 and 60 chains, and at Intersect E. bdy. 12 lks. N. of ¼ sec. cor. Thence N.89°55' W. on true line.</p>
19.92	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
39.85	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.</p>
59.77	<p>Set basalt stone 24x10x10 ins. 18 ins. in the ground for 1/16 sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. and W. of stone, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it.</p>
79.70	<p>To point of beginning. Land, slightly rolling. Soil, 1st rate. All cultivated.</p>
<p>East on random through N. ½ Sec. 12. Va. 21° East.</p>	
<p>Commencing at 1/16 sec. cor., 20 chains N. of ¼ sec. cor. bet. Secs. 11 and 12, set temporary cors. at 20, 40</p>	