

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>East on random through S. <math>\frac{1}{2}</math> of Sec. 35. Va. 21° East.</p> <p>Commencing at 1/16 sec. cor. 20 chains S. of <math>\frac{1}{4}</math> sec. cor. bet. Secs. 34 and 35, set temp. cors. at 20, 40 and 60 chains, and at</p> <p>79.80 Intersect E. bdy. 7 lks. N. of 1/16 sec. cor. Thence N. 89°57' W. on true line.</p> <p>19.95 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>39.90 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>59.00 Fence and enter Indian field.</p> <p>59.85 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p> <p>79.80 To point of beginning.</p> <p>Land, rolling. Soil, good. Partly cultivated.</p> <hr/> <p>East on random through Center of Sec. 35. Va. 21<math>\frac{1}{4}</math>° East.</p> <p>Beginning at <math>\frac{1}{4}</math> sec. cor. bet. Secs. 34 and 35, set temp. cors. at 20, 40 and 60 chains, and at</p> <p>80.00 Intersect E. bdy. 12 lks. S. of <math>\frac{1}{4}</math> sec. cor. Thence S. 89°55' W. on true line.</p> <p>20.00 Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake,</p>
--------	--