

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	
60.15	<p>ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.</p>
80.20	<p>To point of beginning.</p> <p>Land, level.</p> <p>Soil, 1st rate. Not cultivated.</p>
<p>East on random through S ½ of Sec. 26.</p> <p style="text-align: center;">Va. 20° East.</p>	
80.40	<p>Beginning at 1/16 sec. cor. 20 chains N. of SW. cor. of Sec. 26, set temporary cors. at 20, 40 and 60 chains, and at</p> <p>Intersect E. bdy. 12 lks. S of 1/16 sec. cor. Thence S.89°55' W. on true line.</p>
20.10	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
40.20	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long,</p>