

Sub-Subdivisions of T. 3 North, R. 34 East.

Chains	<p>sec. cor. Dug pits 18x18x12 ins. E. and W., stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
37.50	Spring branch, 5 lks. wide, runs SW.
40.10	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
43.00	House, "Dwelling".
60.15	Deposited charred stake 12 ins. in the ground, for 1/16 sec. cors. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.20	To point of beginning. Land, mostly level. Soil, 1st rate. All cultivated.
	<p>East on random through Center of Sec. 23. Va. 21° East. Beginning at ¼ sec. cor. bet. Secs. 22 and 23, set temporary cors. at 20, 40 and 60 chains, and at</p>
80.48	Intersect E. bdy. at ¼ sec. cor. Thence West on true line.
20.12	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in East pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
33.00	Fence bears N. and S.