

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>5½ ft. dist., and raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
80.60	<p>To point of beginning. Land, level. Soil, 1st rate. Partly cultivated. Oct. 5, 1887.</p>
<p>East on random through S ½ of Sec. 14. Va. 21° East.</p>	
<p>Commencing at 1/16 sec. cor., 20 chains N. of SW. cor. of Sec. 14 set temporary cors. at 20, 40 and 60 chains, and at</p>	
80.68	<p>Intersect E. bdy. at 1/16 sec. cor. Thence West on true line</p>
20.17	<p>Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
40.34	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
60.51	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
80.68	<p>To point of beginning. Land, level. Soil, 1st rate. All cultivated.</p>