

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square 12 ins. in the ground, marked 1/16 S on N. face.</p>
79.67	<p>To point of beginning. Land, level. Soil, good.</p>
<p>East on random through N. ½ of Sec. 11. Va. 19¾° East. Beginning at 1/16 sec. cor. 20 chains N. of ¼ sec. cor. bet. Secs. 10 and 11. Set temporary cors. at 20, 40 & 60 chains, and at.</p>	
79.56	<p>Intersect E. bdy. 14 lks. N. of 1/16 sec. cor. Thence N.89°54'W. on true line</p>
14.00	<p>Dwelling of a Mr. Pierce bears S. 10 lks.</p>
19.89	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
39.78	<p>Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
59.67	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
79.56	<p>To point of beginning.</p>