

Sub-Subdivisions of T. 3 North, R. 34 East

Chains 40.15	Set post 3 ft. long, 3 ins. square, 12 ins in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on N. face. Dug pits 18x18x12 ins. E. and W. of post, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around post.
58.00	Leave field.
60.22	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.30	To point of beginning. Land, rolling. Soil, 1st rate. Partly cultivated.
East on random through N. $\frac{1}{2}$ of Sec. 27. Va. 21° East.	
	Commencing at 1/16 sec. cor. 20 chains N. of $\frac{1}{4}$ sec. cor. bet. Secs. 27 and 28, set temporary cors. at 20, 40 and 60 chains, and at
80.40	Intersect E. bdy. 80 lks. N. of 1/16 sec. cor. Thence N.89°26' West on true line.
20.10	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. sq. 12 ins. in the ground, mkd. 1/16 S on N. face.
40.20	Set basalt stone 14x8x6 ins. 10 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face. Dug pits 18x18x12 ins. E. and W. of stone, $5\frac{1}{2}$ ft. dist. Raised md. of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
58.50	Gulch
60.30	Set basalt stone 9x8x7 ins. 6 ins in the ground for 1/16 sec. cor., marked 1/16 on N. face. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound